Preserve

App F IX 4

Previous References 192 (one)

File No 69 28

Serial Nos 57167

Later References

General and Revenue Secretariat.

Serial Nos

Part B for May 29

SUBJECT

Estimate for laying sewerage pipe line in block No 45 of No III drainage area sanctioned by the Board of Trustees

57 To, The Chairman 24 Pgs Municipal Commissioners
No L 7755-6/d 23 5 29

Sanctions the estimate referred to above

Mr 69-28-54

No 1351 Encl duplicate plans Estimate & Plan
6 s 1929

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE

Dated 3rd / 6 May 1929

FROM Y Ramaswami Esquire B A C E
~~Y RAMASWAMI IYER, ESQ., B.A.~~
Chairman City Improvement Trust Board
Mysore

GEN & R&V SECTN
4956
10 MAY 1929
L. S. G BRANCH

OFFICE OF THE
SEC ME COU AL
18 MAY 1929
No 8974

To

The General Secretary to the Government of
His Highness the Maharaja of Mysore
Bangalore

SIR

I have the honour to forward herewith an estimate for laying sewerage pipe line in Block No 45 of No III Drainage area Part II sanctioned by the Board of Trustees at their ordinary meeting held on the 23rd March 1928 and to request that you may be so good as to obtain the sanction of Government thereto

The report accompanying the estimate and plans in duplicate explains the nature and necessity for the work A copy of the Board's Resolution thereon is also forwarded for reference

The cost of the estimate Viz Rs 2 407 will be met out of Rs 4 000 provided in the budget for the current year Vide item No 4 under construction works

I have the honour to be
Sir
Your most obedient servant

Y Ramaswami
Chairman

rate sanctioning Municipalities The cost of estimate is provided the Budget of the Bd. for 28-29 (M O)
H 1575 Jun 17/5

28 17/5

Mr

Second member 18/5
The Chairman, Mysore
No 7255-83 23 5-29
Executive Engineer

GEN & R&V SECTN
30 MAY 1929
Rs & L BRANCH

Mr 21/5

28 21/5

Proceedings of the 9th Ordinary meeting of the Board of Trustees for the Improvement of the City of Mysore held at the Chairman's Office on Saturday the 23rd March 1929 at 8 A M

Present

T C Rama Iyer Esquire B A (Chairman)

1 The Sanitary Commissioner of Mysore
2 The Vice President City Municipal Council Mysore
3 The Health Officer City Municipal Council Mysore
4 Pathakaryaprasakta D K Darasha Esquire B A
5 J E A D'Cruz Esquire A C E F C E

Absent

1 Sir Charles Todhunter K C S I
2 Mahomed Sait Esquire
3 K Dhanakotichetty Esquire

---

x x x x x

XXXIII Estimate for Rs 2 407 for sewerage work in Bloc No 45 No III Drainage area

Sanctioned

x x x x x x x

Sd/ T C Rama Iyer
Chairman

"C O P Y"

Chairman

Report to accompany the estimate for completing the severage system in Block No 45 No 3 Drainage area

---

Amount of estimate Rs 2,407

The area comprising this block is between Sivaramapet Santhepet and Kothval Krishnappa's street This block is included in the budget estimate as being very urgent There is a provision of R 4 CCC for this and Block No 1 If the proposed lines as estimated are carried out this block would be completely severed

Sanction to the estimate is requested

Chairman

MYSORE CITY IMPROVEMENT TRUST BOARD

Estimate for the probable cost of Laying sewerage pipe line in Block No 45 of No 3 drainage area Part II

WD 249—GBPM—500—28 8 8

Particulars of work	No	Dimensions L	B	D	Contents	Total	Unit	Rate Rs	a	p	Amount R	a	p
Earth work excavation and refilling													
sewage soil													
From Man hole 46 to 45	1	70	2½	2½	437								
45 to 48	1	36	2½	3½	315								
48 to 47	1	68	2½	4	680								
A to B	1	74	2½	4	740								
Total					2172	80	cft	—	6		30		
Of galvanized 7 S W Pipe	1	188			188	188	Rft	1	3	9	232		
Of " 7"×4 Junction	1	60			60	60	"	2	12		165		
ing Laying and fitting 7 S W pipe	1	248			248	248	Rft		2	9	43		
Erecting Square Man hole	2				2	2	Each	160			320		
Erecting " W & H	3				3	3	"	150			450		
House connections	30				30	30	"	35			1050		
ing surplus earth	80/6				13	13	cft		3		2		
Total Rupees											2292		
Contingencies at 5%											115		
Grand Total Rupees											2407		

Asst Board Engineer

M Ramadas
Chairman

Carried over

— Mysore City Improvement —

— Trust Board —

Original

Estimate for Laying sewerage pipe
Line in 2nd No 65 of N 3 Nanjaraja La

Amount of Estimate for Rupees 244

G R S VI G 34J

SUBJECT

Diary No of letter replied to 4956

General and Revenue Secretariat

( )

the *192*

Date of issue 23 5 1929

Signed by M V D K S Ayyar

May this be

i Printed ?

ii Entered as a standing order ?

iii published in the Gazette English Part ?

iv translated ?

v placed at the disposal of the press ?

vi published in the Gazette Kannada Part ?

NC

Section Ml

File No 69-28

Serial No 57

Proceedings of the Government of His Highness the Maharaja of Mysore

Read— Letter no 1351 dated the 6th may 1929 from the Chairman City Improvement Trust Board, Mysore soliciting sanction to the resolution of the Board dated the 23rd March 1929, approving an estimate for Rs 2407-0-0 on account of laying sewerage pipe line in Block no 45 of no III Drainage area, part II Order Thereon &c (Mysore city), the cost being met out of the provision of Rs 40007= made under item no 4 of Construction works in the Current year's budget of the Mysore City Impt Trust Bd

Order No L 77556 / Fire & Cem Estimate

of 23rd May 1929

The resolution of the City Improvement Trust Board is dated

23/5/29 To General Secy to Govt

Secy
4/5/29 No 1575

To

The Chairman,
City Impt. Trust Board,
Bangalore with plan & estimate
Comp Adm to Govt

List of enclosures

Copied by

Examined by

WD 1 —G1 B—1 000 00—21 12 3